

ORDINANCE NO. 51-23

AN ORDINANCE AUTHORIZING THE CITY MANAGER TO ACCEPT A CHANGE ORDER FOR THE CONNEAUT CREEK DREDGE RECLAMATION FACILITY, ATTACHED HERETO AND MARKED "CHANGE ORDER NO. 1" AND DECLARING AN EMERGENCY.

BE IT ORDAINED, by the City of Conneaut, County of Ashtabula and State of Ohio:

SECTION 1. That the City Manager, on behalf of the City of Conneaut, is hereby authorized to accept a change order for the Conneaut Creek Dredge Reclamation Facility, attached hereto and marked "Change Order No. 1".

SECTION 2. That it is hereby found and determined that all formal actions of this Council concerning and relating to the passage of this ordinance were adopted in an open meeting of this Council and that all deliberations of this Council or any of its committees that resulted in such formal actions were in meetings open to the public, in compliance with all legal requirements including Section 121.22 of the Ohio Revised Code.

SECTION 3. This Ordinance is declared to be an emergency measure in the interests of public peace, health and safety, and to allow work to continue on the Project, and if approved, shall take effect immediately upon passage.

Passed this 8TH day of MAY, 2023.



President of Council

ATTEST:



Clerk of Council

CHANGE ORDER NO.: 1

DATE: 4/4/2023

PROJECT NAME: Conneaut Creek Dredge Reclamation FacilityOWNER: City of ConneautCONTRACTOR: Independence Excavating, Inc.PROJECT NO.: 180703

DESCRIPTION: Perform subgrade drying/stabilization of the existing coal like subgrade material with quick lime or kiln dust in depths of 12"-18" in various areas with locations and depths being verified in the field in a NTE cost as per the attached proposal.


CONTRACT PRICE:

ORIGINAL CONTRACT PRICE:	<u>\$11,470,000.00</u>
NET PRIOR CHANGE ORDERS:	<u>\$0.00</u>
CURRENT CONTRACT PRICE:	<u>\$11,470,000.00</u>
NET AMOUNT THIS CHANGE ORDER:	<u>\$1,600,000.00</u>
REVISED CONTRACT PRICE:	<u>\$13,070,000.00</u>

CONTRACT TIME:

CONTRACT DATE:	<u>10/11/2022</u>
ORIGINAL COMPLETION DATE:	<u>7/31/2023</u>
CURRENT COMPLETION DATE:	<u>7/31/2023</u>
AMOUNT OF TIME EXTENSION:	<u>0</u>
REVISED COMPLETION DATE:	<u>7/31/2023</u>

ACCEPTED BY:


Daniel Weimer, Project Manager
Independence Excavating, Inc.

4/11/2023
DATE

APPROVALS:

James E. Hockaday
City Manager

DATE

APPROVAL RECOMMENDED BY:

4/12/2023

Christian DeLuca, Project Manager
CT Consultants, Inc.

DATE

OWNER: City of Conneaut			Change Order No.: 1			PROJECT NO.: 180703			DATE: 4/4/2023	
PROJECT: Conneaut Creek Dredge Reclamation Facility										
REF. NO.	ODOT ITEM NO.	DESCRIPTION	CONTRACT		UNIT PRICE	EXTENDED TOTALS	TOTAL		NET CHANGE	
			QTY	UNIT			QTY	\$	QTY	\$
1	201	Clearing and Grubbing	1.00	LS	\$30,000.00	\$30,000.00		\$0.00	(1.00)	(\$30,000.00)
2	202	Remove Concrete Support Columns and Foundations	1.00	LS	\$10,000.00	\$10,000.00		\$0.00	(1.00)	(\$10,000.00)
3	202	Remove Foundations from Prior Building or Conveyor Belt Systems	1.00	LS	\$5,000.00	\$5,000.00		\$0.00	(1.00)	(\$5,000.00)
4	202	Disassemble and Remove Yard Light Tower	1.00	LS	\$2,000.00	\$2,000.00		\$0.00	(1.00)	(\$2,000.00)
5	202	Remove Foundations from Yard Light Tower	1.00	LS	\$2,000.00	\$2,000.00		\$0.00	(1.00)	(\$2,000.00)
6	202	Remove Concrete Barriers and Debris Piles	1.00	LS	\$1,500.00	\$1,500.00		\$0.00	(1.00)	(\$1,500.00)
7	204	Subgrade Compaction	181,832.00	SY	\$1.25	\$227,290.00		\$0.00	(181,832.00)	(\$227,290.00)
8	203	Excavation Including Embankment (In-Situ Soil)	1.00	LS	\$609,458.04	\$609,458.04		\$0.00	(1.00)	(\$609,458.04)
9	203	Borrow (Clay Cap Liner)	108,335.00	CY	\$26.00	\$2,816,710.00		\$0.00	(108,335.00)	(\$2,816,710.00)
10	203	Borrow (Sluiceway and Containment Berms)	167,490.00	CY	\$14.00	\$2,344,860.00		\$0.00	(167,490.00)	(\$2,344,860.00)
11	SPCL	Construction Exit	1.00	EA	\$7,000.00	\$7,000.00		\$0.00	(1.00)	(\$7,000.00)
12	SPCL	Silt Fence	7,400.00	FT	\$3.00	\$22,200.00		\$0.00	(7,400.00)	(\$22,200.00)
13	SPCL	Filter Sock	1,850.00	FT	\$3.50	\$6,475.00		\$0.00	(1,850.00)	(\$6,475.00)
14	SPCL	Concrete Washout Pit	2.00	EA	\$1,200.00	\$2,400.00		\$0.00	(2.00)	(\$2,400.00)
15	659	Seeding and Mulching, Class 6, Temporary Erosion Control	38.00	AC	\$2,250.00	\$85,500.00		\$0.00	(38.00)	(\$85,500.00)
16	671	Erosion Control Mat, Contingency	1,400.00	SY	\$1.00	\$1,400.00		\$0.00	(1,400.00)	(\$1,400.00)
17	SPCL	Sediment Trap	8.00	EA	\$1,000.00	\$8,000.00		\$0.00	(8.00)	(\$8,000.00)
18	616	Water (Dust Control)	630.00	MGAL	\$175.00	\$110,250.00		\$0.00	(630.00)	(\$110,250.00)
19	616	Calcium Chloride	3.00	TON	\$500.00	\$1,500.00		\$0.00	(3.00)	(\$1,500.00)
20	832	Temporary Sediment and Erosion Control	50,000.00	EA	\$1.00	\$50,000.00		\$0.00	(50,000.00)	(\$50,000.00)
21	832	Storm Water Pollution Prevention Plan	1.00	LS	\$35,000.00	\$35,000.00		\$0.00	(1.00)	(\$35,000.00)
22	601	Rock Channel Protection, Type C with Filter	43.00	CY	\$125.00	\$5,375.00		\$0.00	(43.00)	(\$5,375.00)
23	601	Rock Channel Protection, Type D without Filter	5,963.00	CY	\$75.00	\$447,225.00		\$0.00	(5,963.00)	(\$447,225.00)
24	611	Drainage Sump Basin, 2'x2'	4.00	EA	\$1,500.00	\$6,000.00		\$0.00	(4.00)	(\$6,000.00)
25	611	Inlet Structure #1 and Appurtenances	1.00	EA	\$135,000.00	\$135,000.00		\$0.00	(1.00)	(\$135,000.00)
26	611	Outlet Structure #2 and Appurtenances	1.00	EA	\$20,000.00	\$20,000.00		\$0.00	(1.00)	(\$20,000.00)
27	SPCL	Bridge Walkway and Foundation	1.00	EA	\$35,000.00	\$35,000.00		\$0.00	(1.00)	(\$35,000.00)
28	SPCL	Headwall (6" Pipe)	1.00	EA	\$2,500.00	\$2,500.00		\$0.00	(1.00)	(\$2,500.00)
29	638	6" DIPS HDPE DR 21 Pipe, Fusion Joints and Mechanical Fittings	1,535.00	FT	\$38.00	\$58,330.00		\$0.00	(1,535.00)	(\$58,330.00)
30	611	18" Conduit, Type B, 707.33 (HDPE)	188.00	FT	\$90.00	\$16,920.00		\$0.00	(188.00)	(\$16,920.00)
31	638	18" DIPS HDPE DR 11 Pipe, Fusion Joints and Mechanical Fittings	864.00	FT	\$110.00	\$95,040.00		\$0.00	(864.00)	(\$95,040.00)
32	SPCL	6" Quick Couple Connection with Cap	4.00	EA	\$3,000.00	\$12,000.00		\$0.00	(4.00)	(\$12,000.00)
33	638	6" Plug Valve	4.00	EA	\$3,000.00	\$12,000.00		\$0.00	(4.00)	(\$12,000.00)
34	638	6" Plug Valve and Valve Box	1.00	EA	\$5,000.00	\$5,000.00		\$0.00	(1.00)	(\$5,000.00)
35	SPCL	18" Flexible Check Valve	2.00	EA	\$11,458.23	\$22,916.46		\$0.00	(2.00)	(\$22,916.46)
36	304	4" Crushed Limestone Aggregate Base	3,714.00	CY	\$85.00	\$315,690.00		\$0.00	(3,714.00)	(\$315,690.00)
37	304	6" Crushed Limestone Aggregate Base	11.00	CY	\$96.00	\$1,056.00		\$0.00	(11.00)	(\$1,056.00)
38	304	8" Crushed Limestone Aggregate Base	1,777.00	CY	\$80.00	\$142,160.00		\$0.00	(1,777.00)	(\$142,160.00)
39	SPCL	3" Crushed Limestone, No. 57 Aggregate	2,787.00	CY	\$75.00	\$209,025.00		\$0.00	(2,787.00)	(\$209,025.00)
40	204	Proof Rolling	20.00	HR	\$150.00	\$3,000.00		\$0.00	(20.00)	(\$3,000.00)
41	SPCL	12" Crushed Limestone, No. 1 & 2 Aggregate	11,129.00	CY	\$80.00	\$890,320.00		\$0.00	(11,129.00)	(\$890,320.00)
42	204	Geotextile Fabric, Mirafi HP 270	49,140.00	SY	\$2.00	\$98,280.00		\$0.00	(49,140.00)	(\$98,280.00)
43	204	Geotextile Fabric, Mirafi RS380i	8,632.00	SY	\$5.00	\$43,160.00		\$0.00	(8,632.00)	(\$43,160.00)

OWNER: City of Conneaut			Change Order No.: 1			PROJECT NO.: 180703		DATE: 4/4/2023		
PROJECT: Conneaut Creek Dredge Reclamation Facility										
REF. NO.	ODOT ITEM NO.	DESCRIPTION	CONTRACT		UNIT PRICE	EXTENDED TOTALS	TOTAL		NET CHANGE	
			QTY	UNIT			QTY	\$	QTY	\$
44	451	8" Reinforced Concrete Pavement, Class QC1	368.00	SY	\$115.00	\$42,320.00		\$0.00	(368.00)	(\$42,320.00)
45	608	5" Concrete Walk	663.00	SF	\$15.00	\$9,945.00		\$0.00	(663.00)	(\$9,945.00)
46	608	Concrete Steps, Type A, As Per Plan	1.00	LS	\$13,000.00	\$13,000.00		\$0.00	(1.00)	(\$13,000.00)
47	630	Ground Mounted Support, No. 2 Post, U-Channel	54.00	FT	\$25.00	\$1,350.00		\$0.00	(54.00)	(\$1,350.00)
48	630	Sign, Misc.	5.00	EA	\$500.00	\$2,500.00		\$0.00	(5.00)	(\$2,500.00)
49	653	Topsoil Furnished and Placed	3,267.00	CY	\$20.00	\$65,340.00		\$0.00	(3,267.00)	(\$65,340.00)
50	659	Commercial Fertilizer	1.00	TON	\$775.00	\$775.00		\$0.00	(1.00)	(\$775.00)
51	659	Seeding and Mulching, Class 1	29,406.00	SY	\$0.50	\$14,703.00		\$0.00	(29,406.00)	(\$14,703.00)
52	659	Water	20.00	MGAL	\$1.00	\$20.00		\$0.00	(20.00)	(\$20.00)
53	659	Mowing	264,650.00	SF	\$0.01	\$2,646.50		\$0.00	(264,650.00)	(\$2,646.50)
54	SPCL	Bollard, Steel	15.00	EA	\$500.00	\$7,500.00		\$0.00	(15.00)	(\$7,500.00)
55	607	Fence, Type Chain-Link	30.00	FT	\$60.00	\$1,800.00		\$0.00	(30.00)	(\$1,800.00)
56	SPCL	Orange Construction Fence	163,000.00	SY	\$1.00	\$163,000.00		\$0.00	(163,000.00)	(\$163,000.00)
57	SPCL	Concrete Pipe Support with Base	2.00	EA	\$1,700.00	\$3,400.00		\$0.00	(2.00)	(\$3,400.00)
58	SPCL	Concrete Pipe Support and Strip Base	12.00	EA	\$1,000.00	\$12,000.00		\$0.00	(12.00)	(\$12,000.00)
59	SPCL	Trench Dam	2.00	EA	\$325.00	\$650.00		\$0.00	(2.00)	(\$650.00)
60	SPCL	Trailer Mounted Portable Pump	2.00	EA	\$35,000.00	\$70,000.00		\$0.00	(2.00)	(\$70,000.00)
61	619	Field Office, Type A	12.00	MNTH	\$1,500.00	\$18,000.00		\$0.00	(12.00)	(\$18,000.00)
62	SPCL	Special Worker Protection Measures	1.00	LS	\$10.00	\$10.00		\$0.00	(1.00)	(\$10.00)
63	SPCL	Special Worker Orientation Courses and ID Badges	1.00	LS	\$5,500.00	\$5,500.00		\$0.00	(1.00)	(\$5,500.00)
64	SPCL	Bonds and Insurances	1.00	LS	\$350,000.00	\$350,000.00		\$0.00	(1.00)	(\$350,000.00)
65	624	Mobilization	1.00	LS	\$650,000.00	\$650,000.00		\$0.00	(1.00)	(\$650,000.00)
66	SPCL	Marking of Private Utilities	1.00	LS	\$15,000.00	\$15,000.00		\$0.00	(1.00)	(\$15,000.00)
67	SPCL	Preconstruction Video Documentation	1.00	LS	\$5,000.00	\$5,000.00		\$0.00	(1.00)	(\$5,000.00)
68	614	Maintaining Traffic	1.00	LS	\$150,000.00	\$150,000.00		\$0.00	(1.00)	(\$150,000.00)
69	623	Construction Layout Stakes and Surveying	1.00	LS	\$85,000.00	\$85,000.00		\$0.00	(1.00)	(\$85,000.00)
70	SPCL	Inspection and Material Testing	1.00	LS	\$65,000.00	\$65,000.00		\$0.00	(1.00)	(\$65,000.00)
71	SPCL	Railroad Crossing Maintenance Allowance	1.00	LS	\$50,000.00	\$50,000.00		\$0.00	(1.00)	(\$50,000.00)
72	SPCL	Railyard Route Maintenance Allowance: Excavation of Subbase	500.00	CY	\$7.00	\$3,500.00		\$0.00	(500.00)	(\$3,500.00)
73	304	Railyard Route Maintenance Allowance: Crushed Limestone Aggregate Base	500.00	CY	\$65.00	\$32,500.00		\$0.00	(500.00)	(\$32,500.00)
74	204	Site Preparation Allowance: Excavation of Subgrade	5,000.00	CY	\$20.00	\$100,000.00		\$0.00	(5,000.00)	(\$100,000.00)
75	304	Site Preparation Allowance: Crushed Limestone Aggregate Base	5,000.00	CY	\$95.00	\$475,000.00		\$0.00	(5,000.00)	(\$475,000.00)
76	SPCL	Flagger at Railroad Crossing Allowance	1.00	LS	\$100,000.00	\$100,000.00		\$0.00	(1.00)	(\$100,000.00)
CO	SPCL	Change Order #1 Subgrade Stabilization	1.00	LS	\$1,600,000.00	\$1,600,000.00		\$0.00	(1.00)	(\$1,600,000.00)
TOTALS						\$13,070,000.00		\$0.00		(\$13,070,000.00)