SEIBERLING DRIVE

SUBLOT	STORM CONNECTION: WYE DISTANCE FROM DOWNSTREAM MH/BASIN	LENGTH	RISER	WATER CONNECTION: 1" TAP STATION
568	EXTG.	"	"	26+83
587	57'	20'	2	30+02
588	41'	18'	2	30+97
589	EXTG.	"	"	32+03
590	EXTG.	"	"	33+11
591	EXTG.	"	"	34+10
592	EXTG.	"	"	34+90
593	82'	71'	"	31+38
594	5'	70'	"	30+64
595	51'	70'	"	29+97
603	EXTG.	"	"	26+78

C/L CURVE DATA

CURVE	RADIUS	LENGTH	TANGENT	CHORD	BEARING	DELTA
1	500.00	182.27	92.16	181.26	N 57°16'28" E	20°53'11"
2	750.00	196.43	98.78	195.87	N 54°20'03" E	15°00'22"
3	750.00	55.18	27.60	55.17	N 63°56'43" E	04°12'57"

BENCH MARK
TOP OF HYDRANT
STA. 32+60 SEIBERLING DRIVE
ELEV. 1004.56

NOTE:

SANITARY LATERALS AND MAINLINE SANITARY SEWER OVER STORM SEWERS SHALL HAVE LIMESTONE BEDDING BETWEEN THE STORM SEWER AND THE LATERAL OR MAINLINE SANITARY SEWER THE WIDTH OF THE STORM SEWER TRENCH.

SEIBERLING DRIVE

REVISIONS
8/98 C/L PER C.O.S.E.
8/98 PER D.O.E.S.
8/98 PER C.W.D.

APPROVED AS NOTED
BY _____ DATE 9/25/98
SEYMOUR D. WEISS & ASSOCIATES

IMPROVEMENT PLAN & PROFILE
SEIBERLING DRIVE 60' R/W
EATON ESTATE ~ PHASE 15
SAGAMORE HILLS, OHIO

DONALD G. BOHNING & ASSOCIATES, INC.
CIVIL ENGINEERING & SURVEYING
7979 HUB PARKWAY • VALLEY VIEW, OHIO 44125
PHONE: (216) 642-1130 FAX: (216) 642-1132

GRAPHIC SCALE
HORIZ. SCALE 1" = 50'
VERT. SCALE 1" = 5'
DR'N J.H. CK'D. D.G.
DATE MAY, 1998
ORDER NO. 2261-68